

Run Unistrut perpendicular to existing building supports and hang ¼"-20 threaded rod at 4' (nominal) center points.

Grid will hang from the threaded rod and can be leveled with the turn buckles.  
We provide material from the turnbuckle down.

Unistrut and threaded rod cost, per square foot of cleanroom, can vary based on the height of the existing structure vs. the height of the clean room ceiling (e.g.: more or less threaded rod).  
\$1 to \$2 per square foot is usually a safe budget.









